

Tabela robót ziemnych przy budowie ulicy

kilometraż			pow. [m ²]		pow. śr. [m ²]		odleg.	objętość [m ³]		zużycie na	nadmiar objętości		suma	
km	hm	m	W	N	W	N	[m]	W	N	miejsu	[m ³]		objętości	
							-			[m ³]	W	N	W	N
0	0	0.00	9.11	0.00	8.51	0.00	25.00	212.75	0.00	0.00	212.75	0.00	212.75	0.00
0	0	25.00	7.91	0.00									379.38	0.00
					6.67	0.00	25.00	166.63	0.00	0.00	166.63	0.00		
0	0	50.00	5.42	0.00	6.36	0.00							538.25	0.00
							25.00	158.88	0.00	0.00	158.88	0.00		
0	0	75.00	7.29	0.00	8.12	0.00							741.13	0.00
							25.00	202.88	0.00	0.00	202.88	0.00		
0	1	0.00	8.94	0.00	8.28	0.00							782.91	0.00
							5.05	41.79	0.00	0.00	41.79	0.00		
0	1	5.05	7.61	0.00									782.91	0.00
								782.91	0.00	0.00	782.91	0.00		

Podsumowanie wszystkich robót

Suma wykopów	166.63
Suma nasypów	0.00